689

ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

No. 412, *dated* 8*th September* 1928.

"The last date for receiving tenders for restoring Arahatolalu Kakamallanakere, R. No 271 of Shimoga Taluk is extended up to 25th September 1928. The intending contractors may submit their tenders within that date. For details please see page 838 of Part VI of the Gazette, dated 23rd August 1928.

M. A. SRINIVASACHARI,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

NOTIFICATION.

Dated 12*th September* 1928.

Notice is hereby given that sealed tenders will be received up to 5th October 1928, at the Office of the Chief Electrical Engineer, Bangalore, for

(1) Constructing 2 blocks of cooly quarters with 2 units of latrine at Tumkur Town

and

(2) Constructing 2 blocks of cooly quarters with 2 units of latrine at Kolar Town.

The works should be completed within 4 months.

2. The plans, detailed estimates and conditions for item No. (1) may be seen at the Offices of the Chief Electrical Engineer, Bangalore, and the Superintendent, Bangalore Power and Lighting, and for item No. (2) at the Offices of the Chief Electrical Engineer, Bangalore, and the Chief Operator; Kolar Gold Fields, during office hours on all working days.

3. Tenders should be accompanied by a statement in the form annexed showing the rates in words and figures at which the different items will be executed.

4. Tenders will be opened at 2 P.M., on 5th October 1928.

5. Percentages less than or above estimated rates will not be accepted.

6. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed as "Tender for constructing 2 blocks of cooly quarters with 2 units of latrine at Tumkur" and "Tender for constructing 2 blocks of cooly quarters, with 2 units of latrine at Kolar Town" respectively.

7. The final acceptance of the tenders, will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of the tender.

8. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bonds, in default of which his tender will be cancelled and his earnest money forfeited.

9. The name of the successful tenderer will be posted on the notice board of the Chief Electrical Engineer's Office in due course.

10. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

11. On acceptance of one of the tenders, the earnest money on the rejected tenders will be refunded.

12. The construction work should be started within a fortnight from the date of notification of the acceptance.

13. Specifications for work are those recognised by the Mysore Public Works Department and Marryot's specifications.

14. Water for construction should be got at the contractor's own expense.

15. The contractor should bind himself by the conditions of schedule contract of the Electrical Department.

Statement showing the approximate quantities for constructing one block of cooly quarters at Tumkur and at Kolar Towns.

Sl. No.	Description of work	Unit	Quantity
1	Earthwork excavation and filling in basement including a lead of 50'.	C.yd.	33
2a	Lime mortar and stone jelly concrete foundation (proportion of jelly to mortar 2 : 1 and the mortar to be 1 lime to 2½ sand).	C.ft.	303
2b	Coursed rubble stone masonry in mortar, foundation and basement.	,,	847
c	Burnt brick in clay, superstructure	,,	2,460
d	6" plain cornice built of bric in mortar and chunam plastered, etc., complete.	R.ft.	72
e	Stone slabs 4" thick roughly dressed and set in mortar ..	Sq.ft.	159
f	Stone slabs 4" thick roughly dressed for stone pillars including cutting slots to bressummers.	,,	26
g	Chunam plastering 2 coats	Sqr.	53·74
h	Chunam pointing with thread lines	,,	1·01
i	White and colour washing 2 coats	,,	54·75
j	Constructing sinks with drain pipes	Each.	4
k	Stone mortar pestle including fixing charges	,,	4
3	Flooring with 3" concrete and chunam plastered on top ...	Sqr.	7·97
4a	Roofing with 1st Class Mangalore tiles on teakwood reepers 2" x 1" including cement pointing and chunam borders at ends of roof wherever necessary.	,,	11·40
b	Ridge tiles set in mortar and cement pointed	R.ft.	22
c	Ventilating tiles set in mortar and cement pointed ..	Each.	16
5a	Matty wood work wrought and put up with 2 coats of wood oiling.	C.ft.	41·71
b	Galvanized Iron Sheet (24 B. W. G.) doors with teakwood frame, bolts, hinges, etc., complete (frame 4" x 3½").	Sq.ft.	78
c	Galvanized Iron Sheet (24 B. W. G.) windows with iron bars and fittings, complete (frame 3¾" x 3").	,,	70
d	Teakwood ventilators glazed with wire gauge shutters fixed, complete.	,,	24
e	Chacolate painting 2 coats	,,	3·20
6	Galvanized Iron Sheet sunshades with teak frames and paining.	Each.	4

Statement showing the approximate quntities for constructing one block of latrine at Tumkur and at Kolar Towns.

Sl. No.	Description of work	Per	Quantity
1	Earthwork excavation and filling and basement ..	C.yd.	4
2a	Stone in mortar foundation and basement	C.ft.	130
b	Burnt brick in mortar superstructure	,,	196
c	Chunam plastering	Sqr.	4·91
d	Chunam pointing	,,	0·56
e	White and colour washing 2 coats	,,	5·47
f	Cement plastering ½" thick	,,	0·70
g	Tar washing 2 coats	,,	0·63
3	Flooring with 3" concrete and cement plastering ½" thick ...	,,	0·38
4	Fixing outlets. constructing drains, etc.	Item	1 item
5	Providing Galvd. Iron Sheet tubs 12" x 6 "x 6" with handles, etc., complete with tarring.	Each	6

690

Notification dated 12th August 1928.

Tenders for carting materials for one year from the date of acceptance, will be received in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, till 12 noon on 15th October 1928, relating to the Central Stores, Cauvery Power Scheme, near Messrs. Binny's Mills, Bangalore City, as detailed below:—

Tenders should be enclosed in sealed covers and superscribed as—"TENDERS FOR CARTING CONTRACT TO BE OPENED ON THE 15TH OCTOBER 1928."

Each tender must be accompanied with a deposit of Rs. 25 as otherwise the tender will not be accepted.

The successful tenderer will be required to sign a Contract Deed.

The rates to be tendered shall be in the accompanying form and should be entered both in figures as well as in words. The rate quoted by the contractors should be for all kinds of materials such as Iron Poles, Balgi wooden poles and heavy packages. When once the tender is accepted, no special rate will be allowed on any representation for special consideration.

The Departmental help will be given only for loading and unloading in cases where the packages are big and heavy and also when careful handling is required to ensure the safety of the materials; and if the packages are small and can be loaded or unloaded by a few men, the contractor must himself manage. The decision of the Superintendent of Stores, is final in all cases of doubts. If the materials are not promptly carted either from the Railway Stotion or from the Central Stores or from other places, any wharfages or haulage charges and other damages will have to be made good by the Contractor. He must make arrangements to be in touch with the Store-keeper always at the Central Stores and should supply carts whenever called upon to do so.

In case of urgency, the Chief Electrical Engineer or his authorised representative, is at liberty to tarnsport the materials by the Departmental Lorry and the Contractor will have no claim for compensation.

No.	Particulars	Light packages below 800 lbs. Rate per package	Loads weighing 800 lbs. and below. Rate per load	Loads weighing above 800 lbs. up to 1,600 lbs. Rate per load	Loads of over 1,600 lbs. Rate per ton
1	From City Railway Station or Goods Shed to Central Stores and Vice Versa.				
2	From City Railway Station or Goods Shed or Central Stores to (1) Bangalore Power and Lighting Stores, (2) Central Industrial Workshop or (3) Chief Electrical Engineer's Office premises or vice versa.				
3	From Central Stores or Railway Goods Shed or City Railway Station to New "A" Station and vice versa.				
4	From Central Stores or Railway Goods Shed or City Railway Station to "B" Station and vice versa.				
5	From Central Stores or Railway Goods Shed or City Railway Station to "C" Station and vice versa.				
6	From Metre Gauge Goods Shed to Broad Gauge Goods Shed and vice versa.)				
7	From Bangalore Power and Lighting Stores to A., B. and C. Stations and vice versa.				

C. M. CARIAPA,
Offg *Chief Electrical Engineer*